(*h*) That he shall abide by the rules of the department as regards the kindling of fires and shall hold himself responsible for any forest offences committed by his agents, employees or workmen.

(*i*) That he or his men shall not enter the forest after sunset and before sunrise.

(*j*) That he shall maintain a register in the form prescribed by the District Forest Officer showing the number of bamboos removed and shall keep it open for the examination of Forest Officers above the grade of guards.

(*k*) That he understands that the sale does not prohibit the issue of retail licenses at the seigniorage rates or the exercise by the villagers of their rights in the Forests or the exploitation by the department for supply to Government Departments and the Mysore Paper Mills, Ltd.

(*l*) That for any breach of any of the conditions of the contract by the contractor or his agents, the contract shall be void at the option of the District Forest Officer and that the latter may, after issuing to the contractor a notice of cancellation of contract, enforce forfeiture of all or any part of the deposit and shall resell the right or work it departmentally at the risk of the contractor as in clause (2) *supra*. If the deposit or part thereof is forfeited, it shall be immediately made good by the contractor.

M. G. VENKATA RAO,
District Forest Officer.

ENGINEERING DEPARTMENT.

BUILDINGS DIVISION, BANGALORE.

Notification dated 29th November 1938.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Buildings Division, upto 9th December 1938 (2 P.M.) for extending the Second Floor over the Old Public Office Building, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1939.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 1,790 (Rupees one thousand seven hundred and ninety only) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for extending the Second Floor over the Old Public Office Building, Bangalore," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Mysore Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than the estimated rate will not be accepted.

Abstract of estimate for extending Second Floor of Old Public Offices, Bangalore.

No.	Items of work	Unit	Rate	Quantity	Rate to be quoted
1	Dismantling masonry over the first floor terrace, carrying to ground and carting to the halla, 1 mile lead	C.ft.	Rs. a. p. 0 1 0	1,100	

No.	Items of work	Unit	Rate	Quantity	Rate to be quoted
			Rs. a. p.		
2	Burnt brick in mortar	C.ft.	0 6 0	200	
3	Removing and stacking burnt stone slab including cutting	S.ft.	0 2 0	18	
4	Removing and carrying glass shutters to Stores ..	,,	0 0 6	325	
5	Removing corrugated zinc sheet roof with asbestos sheet ceiling including wood work and carting to Store	Sqr.	3 0 0	8·00	
6	Removing the Cast Iron down water pipes 4″ dia. and bends, etc.	R.ft.	0 2 0	79	
7	Wirecut brick in cement 1 : 8	C.ft.	0 12 0	5,533	
8	Wirecut special arch brick in cement 1 : 8 including wooden centering	,,	1 4 0	241	
9	Burnt stone slabs 6″ thick, one line dressed, fixed in cement	S.ft.	0 6 0	52	
10	Burnt stone slab 6″ thick, two line dressed top and front and rear face including fixing in mortar	,,	0 8 0	130	
11	Fixing old slab set in mortar	,,	0 2 0	18	
12	Constructing ornamental circular ¾ dr. pillars with wirecut bricks in cement including ornamental base and capital 7′ high and lime plastering with white and colour washing complete as per existing	Each	10 0 0	22	
13	Dental cornice over pillar 6″ deep and 12″ high, with wirecut bricks in cement and nice plastering as per existing	R.ft.	0 12 0	150	
14	Cornice 3″ deep 6″ raise, with wirecut bricks in cement and nice plastering as per existing ones	,,	0 6 0	120	
15	Cornice 9″ with wirecut bricks in cement and nice plastering	,,	0 10 0	189	
16	Projecting ornamental key for arch centre with mortar as per existing one	,,	1 0 0	10	
17	Teakwood door, ⅓ panelled, ⅔ glazed, ⅛″ thick ground glass panes, 2½″ thick shutters, and special opening in door shutters, top rectangular ventilators, over semi-circular form light frame 4″×5″ with special hinges and acheme brass fittings, rim door lock and finger plate (4″×12″) design as per existing	S.ft.	2 8 0	304	
18	Teakwood door, half shutters with ¼″ thick ground glass panes and spring hinges with brass fittings for door	,,	1 8 0	115	
19	Teakwood ventilators fully glazed with 3″×4″ frames and 1½″ thick shutters 1/16″ thick ground glass panes and brass fittings	S.ft.	1 4 0	36	
20	Roofing with hollow bricks (Yelahanka), reinforced (clear span of 11 feet) 4″ average, thick of surki concrete on top 2 courses of flat tiles and top and bottom nice plastering	Sqr.	85 0 0	18.84	
21	Providing and fixing steel trusses for a clear span inside 39′ outside 42′ feet slope 1 to 8 including hoisting, etc., complete (each 10 cwts.) with two coats of paint, approved colour	Each	150 0 0	5	
22	Teakwood wrought and put up (Mysore Teak) ..	C.ft.	5 0 0	120·00	
23	Roofing with corrugated, Trafford Sheet 3/16″ thick with lap of 6″ and necessary bolts, washers and nuts, etc.	Sqr.	50 0 0	21·15	
24	Providing and fixing Trafford Sheet ridging with bolts, nuts and washers	R.ft.	0 12 0	45	
25	Plastering with lime mortar 1 : 2, two coats over wire cut brick wall including scraping joints ..	Sqr.	4 0 0	95·62	
26	Parapet wall, 9″ thick, 1′—9″ height, with base and top cornice and plastering	R.ft.	1 0 0	140	
27	Providing and fixing ornamental iron railing with cast iron floor and wooden frame top, 2½ feet high	,,	3 0 0	63	

Sl. No.	Items of work	Unit	Rate	Quantity	Rate to be quoted
				Rs. a. p.	
28	Teakwood work, wrought and put up joints of (20¼' 3"×12") for floor	C.ft.	6 0 0	395	
29	Providing and fixing 1½" thick teakwood plank from joists on 2"×1" teak reepers placed 12" apart c to c. for floor and smooth plastering	Sqr.	90 0 0	30·62	
30	Flooring with 1½" cement concrete ½" cement plaster with red cement, diagonal cut 8"×8" ends neat borders over 3" lime concrete and neat polishing after finishing the works ..	Sqr.	25 0 0	9·79	
31	White washing, two coats	,,	0 4 0	50·00	
32	Calicarium wash, two coats	,,	3 0 0	26·16	
33	Cream colour washing, two, coats and one coat of white washing	,,	0 6 0	38·94	
34	Turra Cotta colour washing, two coats and one coat of white washing	,,	0 8 0	105·15	
35	Varnishing, two coats (in Jenson Nikalson) with one coat of wood oiling	,,	8 0 0	9·00	
36	Tarring to wood work, two coats	,,	1 8 0	10·00	
37	Wood oiling, two coats	,,	1 8 0	35·00	
38	Teakwood screen with frame of 2½"×3" panelled shutters including lever arrangements ⅔ panelled, ⅓ glazed 1/16" thick ground glass panes including fixing iron clamps and brass fittings ..	S.ft.	1 8 0	149	
39	White silicate painting, two coats	Sqr.	4 0 0	4·12	
40	Government Lac Factory green painting, three coats	,,	5 0 0	5·32	
41	Providing and fixing cast iron round down water pipe 4" diameter with bend and bell mouths ..	R.ft.	2 0 0	281	
42	Fixing old down water pipe and bends	,,	0 2 0	79	
43	Providing and fixing round wooden step from verandah floor to down floor	No.	25 0 0	4	

B. R. GARUDACHAR,
Executive Engineer.

BANGALORE DIVISION.

Notification dated 28th November 1938.

Sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M. on 19th December 1938 for improving Kattigenahalli tank, Reg. No. 27 of Hoskote Taluk.

2. Tenders in the prescribed form obtainable from the office of the Executive Engineer, Bangalore Division, should be addressed to the Executive Engineer, Bangalore Division, in a sealed cover and superscribed as "Tender for improving Kattigenahalli Tank, Reg. No. 27 of Hoskote Taluk." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a duplicate challan for having credited the deposit amount of Rs. 150 into the treasury under "17 (*a*) P. W. Deposits" or Mysore Government Bonds, duly endorsed at face value or market value, whichever is less, as earnest money. The earnest money of the successful tenderer will be retained as security deposit for the due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 20th December 1938, at 3 P.M. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the Departmental Schedule Contract form after depositing an additional sum of Rs. 150 for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay Specifications (1931).

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Bangalore, on all working days between 11 A.M. and 5 P.M., and may be obtained from that officer on payment of Rs. 3 for each.